## V.V.Giri National Labour Institute Sector -24, Noida (U.P.)

PRG/GEN/09/2017(PartNote)
Dated – 28<sup>th</sup> January 2019

#### **TENDER NOTICE**

The V.V.Giri National Labour Institute invites limited quotations for making connection and cleaning of drainage system of hostel block from experienced agencies specialist in civil / drainage work of this Institute. The details of work and terms & conditions are attached. The Interested agency may see the site and submit their rates as per annexure up to 05<sup>th</sup> February 2019 by 3.00 P.M.

(H.S.Rawat) (Administrative Officer)

M/:	S	•••	•••	•••	•••	•••	• • •	•••	•••		•••	•••		•••	•••	
	•••			•••	•••	•••	•••		•••	•••	•••	•••	•••	•••	•••	

# -Details of Works-

PRG/GEN/09/2017(PartNote)
Dated 25.01.2019

# Subject- Making connection and cleaning of drainage system of Hostel Block.

SI. No.	Details of Work	DSR,2019 CPW	Unit	Rates	Total
1.	Dismantling of old S.W. pipes including breaking of joints and bed concrete stacking of useful materials near the site within 50 m lead and disposal of unserviceable materials into municipal dumps: 450 mm diameter.	19.5.8	05		
2.	Providing and lying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc. complete:  450 mm dia. R.C.C. pipe.	19.6.5.	05		
3.	Constructing brick masonry manhole in cement mortar 1:4 (1 cement: 4 coarse sand) with R.C.C. top slab with 1:2:4 mix (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement: 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design: Inside size 90x80 cm and 45 cm deep including C.I. cover with frame				

			POST AND DESCRIPTION OF THE PARTY OF	
	dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg): With common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	19.7.1 19.7.1.1	01	
	Extra for Depth for manholes: Size 90x80 cm With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	19.8.1 19.8.1	2 meter	
4.	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 liters suctions capacity and 6000 liters water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia up to 300mm dia for all depth.	14.77	70 meter	
5.	GST if any			
	Total amounts			
	GRANI			

Note- The area of above works are tentative can be increase or decrease, the payment will be made on the basis of actual measurement.

Grand total amounts in words	
We hereby confirm that above rates are quoted in my acceptance.	
Completion time of work	
Seal and signature of agency	
Date	



-Annexure -II

# Terms & Conditions of making connection and cleaning of drainage system of Hostel block.

- 1. The agency will ensure that the workmanship and material used should be of superior quality and ISI mark.
- 2. Payment will accordingly be made after satisfactory completion of the work as per measurement basis.
- 3. 10% security amount will be stopped as security up to six month and same will be released if no any defects found during liability period.
- 4. The responsibility of the agency mentioned the executed work till liability period up to six month from the date of completion of work.
- 5. Income tax or other tax will be deducted from the bill as per rule.
- 6. Transportation of material etc. would be responsibility of the agency, any paper / document required in this regards would be arranged by the agency at his own cost.
- 7. The Institute will have right to check incoming material and if materials are found of inferior quality, it will be rejected by the Institute.
- 8. The Institute is not bound to accept the lowest rate or any tender and reserve the right to award the work to any one or divide it between more than one agency at its sole discretion and convenience without assigning any reason.
- 9. The agency must visit the site of works and acquaint thoroughly with all the site condition, which may affect the work before submitting their tender.
- 10. Rates should be quoted as per CPWD DSR -2017 only.
- 11. The agency should be enclosed a site visit certificate stating that he / they have visited the site and has / have fully acquainted with the site condition.
- 12. The rates may be submitted as per guideline along with covering letter and every page verified.
- 13. The site of work is V.V.GIRI NATIONAL LABOUR INSTITUTE, SECTOR-24, NOIDA
- 14. The sealed envelope should be marked for "Making connection and cleaning of drainage system of Hostel block" and submitted send to Administrative Officer, V.V.Giri National Labour Institute, Sector-24, Noida 201301 (U.P.)

(Administrative Officer)

### PRG/GEN/09/2017(PartNote)

"Annexure -III"

#### V.V. GIRI NATIONAL LABOUR INSTITUTE

#### NOIDA

# **Details about agency**

1.	NAME OF FIRM	-	
2.	OFFICE ADDRESS	-	
3.	NAME OF OWNER	-	
4.	OWNER ADDRESS	- 87	
5.	Contact no.		
6.	GST No (Certificate may be attached)	-	
7.	FIRM REGITRATION NO. (IF REFIESTERD CPWD/PWD/MES/OTHER G	OVT.DEPTT.)	
8.	NATURE OF WORKS. (Details may be attached)	_	
9.		-	
10.	BANKER NAME & ADDRESS (Document may be attached)	-	

DATE -

SIGNATURE OF OWNER

PLACE -

SEAL